

WolfPack 4K60 Modular Matrix Switcher

—With TV Wall Function



Chassis Selection: WolfPack Chassis Series

Modular Chassis

Buttons with Lights

2-key fast switch


WEB GUI Control

Dual RS232


- 9x9, 18x18 and 36x36 chassis
- 10ms Seamless switching
- 4K60Hz, HDCP2.2, HDMI2.0, DolbyVision
- DIP Switch for resolution adjustment
- 1 card 1-port
- Android and iOS App Control



9x9 Card Cage



18x18 Card Cage



36x36 Card Cage

Input and output card

4K60 HDMI2.0 Input Card



- 1 card 1 HDMI input
- 18G 4K/60 4:4:4 at 18 GBPS
- HDCP2.2, HDR
- 3.5 mm audio embedded
- 10ms Seamless switching

4K60 HDMI2.0 Output Card



- 1 card 1 HDMI output
- 18G 4K/60 4:4:4 at 18 GBPS
- HDCP2.2, HDR
- 3.5 mm audio de-embedded
- 10ms Seamless switching

WEB Control

Matrix x Wang

Not secure | 192.168.0.80/switch.php

Manager Switch Scene Caption Setup Logout More




The interface displays a 4x4 grid of 16 buttons, numbered 1 to 18. The first button (1) is highlighted in blue. To the right of the grid is a vertical column of five blue buttons, each containing a 3x3 grid of numbers 1, 2, and 3. The bottom section features a 3x4 grid of green buttons, each with a small 'X' icon. Below the grid is a control bar with fields for 'x:' and 'y:', and buttons for 'add' and 'del'.

x: y: add del



WEB Control Operation Steps



Step 1: Type the IP address here


A login form titled 'Please login'. It contains two input fields: the first is for the username, containing the text 'admin'; the second is for the password, containing six dots. Below these fields is a blue button labeled 'Login'. The entire form is enclosed in a red rectangle, with a red arrow pointing from the text 'Step 2: Enter the user name and password, Click to Login' to the bottom of the rectangle.

Step 2: Enter the user name and password,
Click to Login

© 2018 Company, Inc. V1.2.0

[Back to top](#)

WEB Control Operation Steps



TV Wall set up

x: 3 y: 4 add

del

Delete the TV Wall



Set up a 3x4 TV Wall

WEB Control Operation Steps

Matrix x Wang

Not secure 192.168.0.80/switch.php

Manager Switch Scene Caption Setup Logout More

1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18

1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18

Output Buttons

x: 3 y: 4 add del

Step 4: Drag the outputs down to the TV Wall

HDTV SUPPLY



WEB Control Operation Steps



Step 5: Drag the corresponded outputs to the TV Wall until it's all full filled

3x4 TV Wall

WEB Control Operation Steps



WEB Control Operation Steps

